



**BOTTOM AND ALL SIDES OF CUT TO BE PREPPED
WITH ASPHALT PRIOR TO PLACING ASPHALT MIX.**

(To be used for pavement additions an utility repairs)

NOTES:

1. Subgrade to be compacted to 95% of maximum density as determined by AASHTO T-99, within plus or minus 20% of optimum moisture content.
2. Contractor to provide a clean straight cut of existing pavement and verify and match existing pavement section as a minimum.

NTS

Date: 6-3-2013